BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/RD/WORK_INDENT16470

APPROVED SCHEDULE - B

Tender Notification EE/BTP/BBMP/E-PMT/08/2014-15, Date: 30.12.2014

Providing CC Road at Kodigehalli Village Surroundings in Ward no 08, Kodigehalli Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of LAKSHMINARAYAN V	
				In Figures	In Words
1	162.75	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after	Cum	75.6	Rupees Seventy Five and Sixty Paise Only
2	290.4	Removing B.S Slab of Drain and stacking including cost of all labour, HOM of machineries etc complete as per	sqm	58.32	Rupees Fifty Eight and Thirty Two Paise Only
3	290.4	Refixing stone slabs of drains and pointing in C.M (1:3) including cost of all labour, HOM of machineries etc	sqm	75.6	Rupees Seventy Five and Sixty Paise Only
4	95.5	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4847.04	Rupees Four Thousand Eight Hundred Forty Seven and Four Paise Only
5	46.25	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc	Cum	5852.52	Rupees Five Thousand Eight Hundred Fifty Two and Fifty Two Paise Only
6	462.5	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc complete as per specifications and directions of engineer in charge of the work	Sqm	97.2	Rupees Ninety Seven and Twenty Paise Only
7	37	Providing groove cutting for cement pavement wifth of 5mm to 10mm and depth 800mm-100mm including cost of cutting machine, generator and HOM of machinery, including cost of blade, coolant etc, including cleaning of groove and providing sand and hot bitumen fillarsm and filler metal etc including of conveyance of all materials, labour, lead and lift charges and all other incidental charges	Rm	124.2	Rupees One Hundred Twenty Four and Twenty Paise Only
8	10.8	Providing and constructing granite / trap / basalt size stone masonry in superstructure with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications	cum	4773.6	Rupees Four Thousand Seven Hundred Seventy Three and Sixty Paise Only
9	16	Providing ruled pointing to coursed stone masonry with cement mortar 1:4, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour,	sqm	92.88	Rupees Ninety Two and Eighty Eight Paise Only
10	4.8	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size	cum	5327.64	Rupees Five Thousand Three Hundred Twenty
11	4.14	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm	cum	6065.28	Rupees Six Thousand Sixty Five and Twenty
12	3.73	Providing mild steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position,	Qtl	7975.8	Rupees Seven Thousand Nine Hundred

13	12.26	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface	sqm	292.55	Rupees Two Hundred Ninety Two and Fifty Five
14	162.75	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and	cum	70.55	Rupees Seventy and Fifty Five Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

'DTS' ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು